



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY

REGION III

841 Chestnut Building  
Philadelphia, Pennsylvania 19107

ORIGINAL  
(Reg)  
*Paul,*  
*your copy*

[REDACTED]  
Environmental Services Assistant  
BDC - Environmental, Inc.

MAR 22 1990

PA-2135

The following information and disposition are furnished concerning your request made under the Freedom of Information Act.

Date Request Received: 1-23-90.

Request Identification Number: 3RIN-181,244,246 & 249-90.

(Estimated Cost): \$177.50.

- ( X ) Positive Determination (Material enclosed).
- ( ) Requested information is not known to exist or is not in EPA's possession. (See remarks below).
- ( ) Requestor reviewed files on \_\_\_\_\_.
- ( ) Your request of \_\_\_\_\_ modified as a result of a discussion with \_\_\_\_\_.
- ( ) Holding Material Pending Receipt of Payment (estimated cost over \$250 or arrangement for payment).
- ( ) Fee Waiver. Less than \$25.00.
- ( ) Processing Request: Extension until \_\_\_\_\_ needed due to \_\_\_\_\_.
- ( X ) Please see attached bill. Make check payable to U. S. Environmental Protection Agency. Put Request Identification Number (RIN) on check and mail to EPA-Region 3, P. O. Box 360515M, Pittsburgh, PA 15251.



COMMONWEALTH OF PENNSYLVANIA  
DEPARTMENT OF ENVIRONMENTAL RESOURCES

Preliminary Assessment

FOR

GELCO TRUCK LEASING  
PA #2135

Bensalem Township  
Bucks County  
Pennsylvania

ORIGINAL  
(Red)

## Gelco Truck Leasing

### Narrative Summary

Gelco Truck Leasing is located in the I-95 Industrial Park on Dunksferry Rd. in Bensalem Township, Bucks County, Pa. Gelco leases various types of trucks, tractor trailers, and tankers for industrial and commercial uses.

The property is leased by Gelco from Diputs, Inc. of Beverly, N.J. Diputs is owned in part by Doris Bell. Mrs. Bell's brother, Gus Propper, operated a waste hauling business from this location in the 1960's and early 1970's. Propper was involved in several instances of illegal waste disposal, including a case in which he was convicted of dumping volatile organic wastes into the sanitary sewer system via a drain inside the building.

Gelco began leasing the property in the late 1970's. Only light truck maintenance such as oil changes is performed at this location. Waste oil was piped from inside the building to an outside underground holding tank. Several overflows from this tank prompted its removal in May 1986. During the removal of the tank and oil-contaminated soil, another large underground tank (fashioned from an old railroad tank car) was discovered about 20 feet away from the terminal building. This tank was apparently used as a holding tank for chemical waste during Gus Propper's operations at the site. A 3" pipe leads from the tank back to the building. The tank was found to contain a black liquid material which included benzene, ethylbenzene, toluene, xylene, 1,1,1 trichloroethane, and tetrachloroethane.


A waste removal firm, O.H. Materials, was contracted to clean up both the oil spill and the buried tank car contents, with the work costs being split between Gelco for the oil spill and Diputs for the tank car. As of this date, the oil cleanup has been completed. Approximately 5000 gallons of material has been pumped from the tank car, but the completion of this portion has been delayed due to non-payment by Diputs for the work performed. The work is set to resume in late December 1986 or January 1987.

Gelco is located about one half mile north of the Delaware River and one mile west of Neshaminy Creek. Groundwater movement is presumably south towards the river. The area is primarily industrial, but there is a small residential area to the south which has been gradually split by the industrial development. Water supply for the area is from Bensalem Township Water and Sewer Authority. The authority purchases water from the city of Philadelphia. The city's Torresdale intake is located on the Delaware approximately four miles downstream. There are no known groundwater users within a half mile radius of the site.

ORIGINAL  
(Red)

The need for a site inspection at Gelco depends on several factors. The completion of the cleanup project by OH Materials is necessary to determine if there is any soil and groundwater contamination around the buried tank car. If the tank is sound and the waste has been adequately contained, no further action would be necessary. If contamination were evident outside the tank, it might be necessary to drill wells for groundwater monitoring, as there are no sampling points in the vicinity. This may not be justifiable since groundwater is not used for drinking in the area. If wells are drilled by Gelco and/or Diputs, then a low priority inspection might be appropriate.

ORIGINAL  
(Red)

		POTENTIAL HAZARDOUS WASTE SITE PRELIMINARY ASSESSMENT PART 1 - SITE INFORMATION AND ASSESSMENT		I. IDENTIFICATION	
				01 STATE PA	02 SITE NUMBER 2135
<b>II. SITE NAME AND LOCATION</b>					
01 SITE NAME (Legal, common, or descriptive name of site) Gelco Truck Leasing		02 STREET, ROUTE NO., OR SPECIFIC LOCATION IDENTIFIER 714 Dunksferry Rd.			
03 CITY Bensalem	04 STATE Pa.	05 ZIP CODE 19020	06 COUNTY Bucks	07 COUNTY CODE	08 CONG DIST
09 COORDINATES LATITUDE 40 04 27		LONGITUDE 74 55 45			
10 DIRECTIONS TO SITE (Starting from nearest public road) I-95 north to Pa. 132 (Street Rd.) to I-95 Industrial Park					
<b>III. RESPONSIBLE PARTIES</b>					
01 OWNER (If known) Diputs, Inc.		02 STREET (Business, mailing, residential) 19 Riverbank Rd.			
03 CITY Beverly	04 STATE NJ	05 ZIP CODE 08010	06 TELEPHONE NUMBER ( )		
07 OPERATOR (If known and different from owner) Gelco Truck Leasing		08 STREET (Business, mailing, residential)			
09 CITY	10 STATE	11 ZIP CODE	12 TELEPHONE NUMBER ( )		
13 TYPE OF OWNERSHIP (Check one) <input checked="" type="checkbox"/> A. PRIVATE <input type="checkbox"/> B. FEDERAL: _____ (Agency name) <input type="checkbox"/> C. STATE <input type="checkbox"/> D. COUNTY <input type="checkbox"/> E. MUNICIPAL <input type="checkbox"/> F. OTHER: _____ (Specify) <input type="checkbox"/> G. UNKNOWN					
14 OWNER/OPERATOR NOTIFICATION ON FILE (Check all that apply) <input type="checkbox"/> A. RCRA 3001 DATE RECEIVED: _____ MONTH DAY YEAR <input type="checkbox"/> B. UNCONTROLLED WASTE SITE (CERCLA 103 c) DATE RECEIVED: _____ MONTH DAY YEAR <input checked="" type="checkbox"/> C. NONE					
<b>IV. CHARACTERIZATION OF POTENTIAL HAZARD</b>					
01 ON SITE INSPECTION <input checked="" type="checkbox"/> YES DATE 10/27/86 MONTH DAY YEAR <input type="checkbox"/> NO		BY (Check all that apply) <input type="checkbox"/> A. EPA <input type="checkbox"/> B. EPA CONTRACTOR <input checked="" type="checkbox"/> C. STATE <input type="checkbox"/> D. OTHER CONTRACTOR <input type="checkbox"/> E. LOCAL HEALTH OFFICIAL <input type="checkbox"/> F. OTHER: _____ (Specify) CONTRACTOR NAME(S): _____			
02 SITE STATUS (Check one) <input type="checkbox"/> A. ACTIVE <input checked="" type="checkbox"/> B. INACTIVE <input type="checkbox"/> C. UNKNOWN		03 YEARS OF OPERATION BEGINNING YEAR _____ ENDING YEAR _____ <input checked="" type="checkbox"/> UNKNOWN			
04 DESCRIPTION OF SUBSTANCES POSSIBLY PRESENT, KNOWN, OR ALLEGED Various aromatic hydrocarbons and other organics					
05 DESCRIPTION OF POTENTIAL HAZARD TO ENVIRONMENT AND/OR POPULATION Potential soil and groundwater contamination					
<b>V. PRIORITY ASSESSMENT</b>					
01 PRIORITY FOR INSPECTION (Check one. If high or medium is checked, complete Part 2 - Waste Information and Part 3 - Description of Hazardous Conditions and Incidents) <input type="checkbox"/> A. HIGH (Inspection required promptly) <input type="checkbox"/> B. MEDIUM (Inspection required) <input checked="" type="checkbox"/> C. LOW (Inspect on time available basis) <input type="checkbox"/> D. NONE (No further action needed, complete current disposition form)					
<b>VI. INFORMATION AVAILABLE FROM</b>					
01 CONTACT Robert Allen		02 OF (Agency/Organization) Pa. DER Bureau of Waste Mgmt.		03 TELEPHONE NUMBER 215/565-1687	
04 PERSON RESPONSIBLE FOR ASSESSMENT 11	05 AGENCY	06 ORGANIZATION	07 TELEPHONE NUMBER ( )	08 DATE 12/10/86 MONTH DAY YEAR	

ORIGINAL  
(Red)

**POTENTIAL HAZARDOUS WASTE SITE  
PRELIMINARY ASSESSMENT  
PART 2 - WASTE INFORMATION**

**I. IDENTIFICATION**

01 STATE 02 SITE NUMBER

**II. WASTE STATES, QUANTITIES, AND CHARACTERISTICS****01 PHYSICAL STATES** (Check all that apply)

- ☐ A. SOLID  
☐ B. POWDER, FINES  
☒ C. SLUDGE  
☐ D. OTHER \_\_\_\_\_  
 (Specify)
- ☒ E. SLURRY  
☒ F. LIQUID  
☐ G. GAS

**02 WASTE QUANTITY AT SITE**  
(Measures of waste quantities must be independent)

TONS \_\_\_\_\_

CUBIC YARDS \_\_\_\_\_

NO. OF DRUMS \_\_\_\_\_

**03 WASTE CHARACTERISTICS** (Check all that apply)

- ☒ A. TOXIC  
☐ B. CORROSIVE  
☐ C. RADIOACTIVE  
☐ D. PERSISTENT
- ☐ E. SOLUBLE  
☐ F. INFECTIOUS  
☐ G. FLAMMABLE  
☐ H. IGNITABLE
- ☒ I. HIGHLY VOLATILE  
☐ J. EXPLOSIVE  
☐ K. REACTIVE  
☐ L. INCOMPATIBLE  
☐ M. NOT APPLICABLE

**III. WASTE TYPE**

CATEGORY	SUBSTANCE NAME	01 GROSS AMOUNT	02 UNIT OF MEASURE	03 COMMENTS
SLU	SLUDGE			
OLW	OILY WASTE			
SOL	SOLVENTS	*		*5000 gal. were removed
PSD	PESTICIDES			from tank-unknown amt.
OCC	OTHER ORGANIC CHEMICALS	*		remains
IOC	INORGANIC CHEMICALS			
ACD	ACIDS			
BAS	BASES			
MES	HEAVY METALS			

**IV. HAZARDOUS SUBSTANCES** (See Appendix for most frequently cited CAS Numbers)

01 CATEGORY	02 SUBSTANCE NAME	03 CAS NUMBER	04 STORAGE/DISPOSAL METHOD	05 CONCENTRATION	06 MEASURE OF CONCENTRATION
occ	xylene	1330-20-7	underground tank	73.0	ppm
"	toluene	108-88-3	"	24.0	"
sol	trichloroethane	25323-89-1	"	0.7	"
"	tetrachloroethane	127-18-4	"	1.4	"
occ	benzene	71-43-2	"	0.6	"

**V. FEEDSTOCKS** (See Appendix for CAS Numbers)

CATEGORY	01 FEEDSTOCK NAME	02 CAS NUMBER	CATEGORY	01 FEEDSTOCK NAME	02 CAS NUMBER
FDS			FDS		
FDS			FDS		
FDS			FDS		
FDS			FDS		

**VI. SOURCES OF INFORMATION** (Cite specific references, e.g., state files, sample analysis, reports)

Sample analysis

# FIELD TRIP : SUMMARY REPORT


This summary should be prepared in conjunction with the Preliminary Assessment, Form 2070-12.

ORIGINAL  
EPA  
(Red)

EPA Case Number \_\_\_\_\_ Site Name Gelco Truck Leasing

<b>Site Description</b>  Truck leasing terminal formerly used for a chemical waste hauling business		
<b>Area of site (acres)</b>  Appr. 1 acre	<b>Hazardous portion, if not entire site</b>  Abandoned underground tank	
<b>Description of processes/operations which took place at the site</b>  Leasing of trucks, trailers, tankers-includes light maintenance, oil changes, refueling, washing, etc.  Previous operations unknown in detail-no records available		
<b>Waste handling/disposal practices</b>  Waste oil drained from inside building to an outside holding tank-oil was then hauled away. Several overflows resulted in soil contamination.  Chemical waste was previously dumped into the sanitary sewer system and into an underground holding tank.		
<b>Site topography and runoff drainage patterns</b> Filled land, 0-3% slope. Drainage is to adjacent roads and storm sewers.		
<b>Surface or subsurface drainage areas (if any)</b> None	<b>Accidents noted?</b>	<b>Odors/stains noted?</b> None <b>Stressed vegetation noted?</b> None
<b>Location and description of streams or flow direction and observations. Note location on attached map.</b>  None		
<b>Monitoring wells on site or in vicinity</b>  None		
Note location on attached map.		

ORIGINAL  
(Red)



Description of odor/taste problems

None

State inspection activity (including permits held)

None

State/Federal/Private remedial activities

See narrative



ORIGINAL  
(Red)

Additional comments--Further description of site

## SITE CONTACTS

Name and Title	Affiliation	Phone
Terry Russell	Gelco	(301) 646-0515
Ken Olsen	"	(609) 272-9696

## INSPECTION INFORMATION

Name and title of inspector(s) Robert AllenAgency Pa. DER Phone number (215) 565-1687Date 10-27-86 Time on site 1 hr.

Weather conditions:

## ATTACHMENTS

- o Topographic map identifying site location. Include name of quadrangle map.
- o Site sketch map showing location of monitoring wells, domestic wells, municipal water supplies, and areas of concern (lagoons, leachate seeps, drums, etc.)
- o Any available sampling results or state monitoring data with map showing sample locations.

Subject: GELCO Site Meeting, 5/30/86 Bensalem Twp.  
Bucks Co.

To:

From:



Attached is the following: Test analysis for liquid sampled in the buried, stacked-rim sump, oil collected at the outside of the building wall, a soil sample collected from the area where the waste oil tank was excavated, List of meeting participants.

Based on the analysis it has been determined that both the sump contents and oil, soil are hazardous. GELCO will be taking responsibility for the oil/soil removal and Frank Bell of Diputis will be responsible for the sump contents.

O.H. Materials will be the consultant to start the following work items on Tuesday, June 3:

- ① excavate & stockpile oil & oil contam. soil on sheet pias
- ② explore exposed piping to determine source(s)
- ③ pump sump contents into a tanker
- ④ O.H. Materials wishes to confer with a DER hydro-geologist on monitoring well cite locations.

PARAMETER	RESULTS mg/kg	PARAMETER	RESULTS mg/kg
<u>ACID EXTRACTABLES</u>		<u>BASE/NEUTRAL FRACTION</u>	
2-Chlorophenol	2.5U	Hexachlorobenzene	1.U
4-Chloro-3-methylphenol	2.5U	Hexachlorobutadiene	1.U
2,4-Dichlorophenol	2.5U	Hexachlorocyclopentadiene	1.U
2,4-Dimethylphenol	2.5U	Hexachloroethane	5.U
2,4-Dinitrophenol	25.U	Indeno(1,2,3-c,d)pyrene	1.U
4,6-Dinitro-2-methylphenol	2.5U	Isophorone	1.U
2-Nitrophenol	2.5U	Naphthalene	2.D
4-Nitrophenol	2.5U	Nitrobenzene	1.U
Pentachlorophenol	2.5U	N-Nitrosodimethylamine	1.U
Phenol	2.5U	N-Nitrosodiphenylamine	1.U
2,4,6-Trichlorophenol	2.5U	N-Nitrosodipropylamine	1.U
		Phenanthrene	8.
		Pyrene	16.
		1,2,3-Trichlorobenzene	1.U
<u>BASE/NEUTRAL FRACTION</u>		<u>VOLATILE FRACTION</u>	
Acenaphthene	1.	Benzene	0.5U
Acenaphthylene	1.	Bromodichloromethane	0.5U
Anthracene	**	Bromoform	0.5U
Benzidine	5.U	Bromomethane	0.5U
Benz(a)anthracene	7.	Carbon tetrachloride	0.5U
Benzo(b)fluoranthene	***	Chlorobenzene	0.5U
Benzo(k)fluoranthene	3.	Chlorodibromomethane	0.5U
Benzo(g,h,i)perylene	2.D	Chloroethane	0.5U
Benzo(a)pyrene	4	2-Chloroethyl vinyl ether	0.5U
Benzyl butyl phthalate	1.U	Chloroform	1.8
4-Bromophenyl phenyl ether	1.U	Chloromethane	0.5U
bis(2-Chloroethyl)ether	1.U	1,1-Dichloroethane	0.5U
bis(2-Chloroethoxy)ether	1.U	1,2-Dichloroethane	0.5U
bis(2-Chloroisopropyl)ether	1.U	1,1-Dichloroethene	0.5U
2-Chloronaphthalene	1.U	trans-1,2-Dichloroethene	0.5U
4-Chlorophenyl phenyl ether	1.U	1,2-Dichloropropane	0.5U
Chrysene	***	cis-1,3-Dichloropropene	0.5U
Dibenzo(a,h)anthracene	4.U	trans-1,3-Dichloropropene	0.5U
Di-n-butyl phthalate	1.U	Ethylbenzene	0.5U
1,2-Dichlorobenzene	1.U	Fluorotrichloromethane	0.5U
1,3-Dichlorobenzene	1.U	Methylene Chloride	34.8
1,4-Dichlorobenzene	1.U	1,1,2,2-Tetrachloroethane	0.5U
3,3'-Dichlorobenzidine	1.U	Tetrachloroethene	0.5U
Diethyl phthalate	2.5U	Toluene	0.8
Dimethyl phthalate	1.U	1,1,1-Trichloroethane	0.5U
2,4-Dinitrotoluene	1.U	1,1,2-Trichloroethane	0.5U
2,6-Dinitrotoluene	1.U	Trichloroethene	0.5U
Di-n-octyl phthalate	1.U	Vinyl Chloride	0.5U
1,2-Diphenylhydrazine	1.U	Total Xylenes	0.5U
bis(2-ethylhexyl)phthalate	9.		
Fluoranthene	21.		
Fluorene	1.U		

CLIENT: O. H. Materials

SAMPLE I.D. 05-1686-18

CLIENT I.D.: Ben Salem, PA Gelco

FRN NO.: &gt;A0011/&gt;B0053

Simp  
ORIGINAL  
(Red)

PARAMETER	RESULTS mg/kg	PARAMETER	RESULTS mg/kg
<u>ACID EXTRACTABLES</u>		<u>BASE/NEUTRAL FRACTION</u>	
2-Chlorophenol	50.U	Hexachlorobenzene	20.U
4-Chloro-3-methylphenol	50.U	Hexachlorobutadiene	20.U
2,4-Dichlorophenol	50.U	Hexachlorocyclopentadiene	100.U
2,4-Dimethylphenol	50.U	Hexachloroethane	20.U
2,4-Dinitrophenol	500.U	Indeno(1,2,3-c,d)pyrene	80.U
4,6-Dinitro-2-methylphenol	50.U	Isophorone	20.U
2-Nitrophenol	50.U	Naphthalene	20.U
4-Nitrophenol	50.U	Nitrobenzene	20.U
Pentachlorophenol	50.U	N-Nitrosodimethylamine	20.U
Phenol	50.U	N-Nitrosodiphenylamine	20.U
2,4,6-Trichlorophenol	50.U	N-Nitrosodipropylamine	20.U
		Phenanthrene	20.U
		Pyrene	20.U
		1,2,3-Trichlorobenzene	20.U
<u>BASE/NEUTRAL FRACTION</u>		<u>VOLATILE FRACTION</u>	
Acenaphthene	20.U	Benzene	0.6
Acenaphthylene	20.U	Bromodichloromethane	0.5U
Anthracene	**	Bromoform	0.5U
Benzidine	100.U	Bromomethane	0.5U
Benz(a)anthracene	20.U	Carbon tetrachloride	0.5U
Benzo(b)fluoranthene	***	Chlorobenzene	0.5U
Benzo(k)fluoranthene	20.U	Chlorodibromomethane	0.5U
Benzo(g,h,i)perylene	80.U	Chloroethane	0.5U
Benzo(a)pyrene	20.U	2-Chloroethyl vinyl ether	0.5U
Benzyl butyl phthalate	20.U	Chloroform	1.2B
4-Bromophenyl phenyl ether	20.U	Chloromethane	0.5U
bis(2-Chloroethyl)ether	20.U	1,1-Dichloroethane	0.5U
bis(2-Chloroethoxy)ether	20.U	1,2-Dichloroethane	0.5U
bis(2-Chloroisopropyl)ether	20.U	1,1-Dichloroethene	0.5U
2-Chloronaphthalene	20.U	trans-1,2-Dichloroethene	0.5U
4-Chlorophenyl phenyl ether	20.U	1,2-Dichloropropane	0.5U
Chrysene	***	cis-1,3-Dichloropropene	0.5U
Dibenzo(a,h)anthracene	80.U	trans-1,3-Dichloropropene	0.5U
Di-n-butyl phthalate	20.U	Ethylbenzene	7.8
1,2-Dichlorobenzene	20.U	Fluorotrichloromethane	0.5U
1,3-Dichlorobenzene	20.U	Methylene Chloride	29.8
1,4-Dichlorobenzene	20.U	1,1,2,2-Tetrachloroethane	1.4
3,3'-Dichlorobenzidine	50.U	Tetrachloroethene	0.5U
Diethyl phthalate	20.U	Toluene	24.
Dimethyl phthalate	20.U	1,1,1-Trichloroethane	0.7
2,4-Dinitrotoluene	20.U	1,1,2-Trichloroethane	0.5U
2,6-Dinitrotoluene	20.U	Trichloroethene	0.5U
Di-n-octyl phthalate	20.U	Vinyl Chloride	0.5U
1,2-Diphenylhydrazine	20.U		
bis(2-ethylhexyl)phthalate	20.U		
Fluoranthene	20.U		
Fluorene	20.U		
		Total Xylenes	73.



THE ENVIRONMENTAL SERVICES COMPANY

ORIGINAL  
(Red)

O. H. MATERIALS CO.

P.O. Box 41

Mon St

Weymouth, NJ 08093-0041

Phone (609) 444-7800

Telex 950000 O H M

**DRAFT**

June 4, 1986

Mr. Terry Russell  
Gelco Corporation  
Expressway 95 Industrial Park  
Ben Salem, PA 19007

Dear Mr. Russell:

O.H. Materials Corp. (OHM) is pleased to be of service to you and your organization. This letter is intended to provide you and Mr. Bell with an outline of work to be performed at your Ben Salem, Pennsylvania facility.

OHM will perform the following work as discussed in our Friday, May 30, meeting:

- o Excavate visually contaminated soil along the foundation of the truck terminal
- o Stage contaminated material on impermeable plastic sheeting which will be surrounded by berms and covered at the end of work each day
- o Excavation will commence at the foundation of the terminal building and continue out parallel to the foundation toward the sump area.
- o Excavation will continue until all visually contaminated material has been removed
- o Clean soil will be segregated and staged to be used as backfill
- o The excavation will extend down as far as contamination is visible
- o The excavation will extend out to the sump area as needed
- o The liquids from the sump area will be pumped and the liquid waste stored on site in 55 gallon 17-E drums
- o Excavation will continue to determine the size of the sump

Mr. Terry Russell

-2-

June 4, 1986

ORIGINAL  
(Red)

- o Excavation will extend down approximately nine feet around the sump
- o Contaminated soil will be staged with the soil removed from along the building
- o OHM will cease excavation when the size and depth of the underground sump has been determined
- o When the approximate size and depth of the sump has been determined OHM will stop all excavation and meet with GELCO representative to determine the best remedial approach to take

OHM will perform the outlined work for an estimated daily cost of \$2,300.00 for each eight hour day or \$3,000.00 for each ten hour day.

If you have any questions, or if you need additional information regarding this project, please feel free to contact me at our New Jersey office at (609) 443-2800 and I will be happy to assist you in any way I can.

Sincerely,

Kevin S. Wood  
Project Manager

KSW:jl

pc: Project Job File 3814

**DRAFT**

ORIGINAL  
(Red)

Department of Environmental Resources

1875 New Hope Street  
Morristown, PA 19401  
215 270-1948

May 21, 1986

*Frank's home # 609-  
387-7535*

Mrs. Bell  
Diputs, Inc.  
19 Riverbank Road  
Beverly, New Jersey 08010

Re: Celco Facility  
714 Dunkaserry Road  
Sewanlen, PA 19020

Dear Mrs. Bell:

This letter is to inform you as owner, or owner representative, of an existing situation at the referenced property, in which the Department has regulatory authority.

Outside of the building there is an area against the building wall where a waste oil storage tank has been removed. There is an accumulation of what appears to be oil, collecting and pooling against the building. Celco Truck Leasing has indicated that they will take the necessary measures to collect and remove this oil and oil contaminated soil.

Additionally, a buried vertical column of truck wheel rims has been discovered approximately 20 feet from the building wall. This "well" contains a nine foot column of an unidentified black and odorous liquid. Entering this stack of rims is a three inch metal pipe in-line with the Celco building.

During an on-site investigation the Department could not determine the inlet of this three inch pipe, but it is surmized that its source is within the building and may have been covered over with concrete.

We understand Celco is conducting a sampling and analysis of these two areas to determine their identities and add in isolating problem areas. As owner/representative you are required to provide the Department with a proposal to correct these disposal violations.

We expect that such a proposal would identify the following:

- method of collection, transportation and disposal location of contaminants

ORIGINAL  
(Red)

Mrs. Ball  
May 21, 1986  
- 2 -

- procedures to determine source of contaminants
- method to render well and piping system useless
- monitoring well locations, design and protocol to establish and conduct a monitoring program to determine extent of migration of contaminants and the potential for remediation

Because Celco has an interest in the waste oil cleanup portion of this matter and has established a response, we encourage you to maintain dialogue with Celco in order to expedite this cleanup project.

Please call us at 215-270-1968 if you have any questions in this regard.

Very truly yours,



MICHAEL M. ROBEC  
Waste Management Specialist





ORIGINAL  
(Red)

Department of Environmental Resources

1875 New Hope Street  
Morristown, PA 19801  
215 270-1928

*June 4. Proposal from OH Materials  
Terri Russell*

June 27, 1986

*...55 gal drum...  
...excavate 9' around sump...*



Re: Celco Facility  
718 Dunkerferry Road  
Pencader, PA

NOTICE OF VIOLATION



This letter is to notify you and your client, Niputs, Inc. of the following violations of the Pennsylvania Hazardous Waste Regulations at the referenced property.


75.262(g) It has become apparent that the liquid wastes stored in an underground tank are hazardous and have been held on-site in excess of 90 days. Accumulation of wastes in excess of 90 days constitutes "storage" and this facility has not met the requirements of 75.262.

75.262(m)(5) Generators of hazardous waste are responsible for developing and implementing a contingency plan to minimize potential for hazardous waste spills and discharges. Lack of secondary containment, and performance of periodic inspections of tank and appurtenances have not been performed and are typical requirements for tank storage operation.

You are hereby notified of both the existence of these violations as well as the need to provide for their prompt correction. Toward this end, you are requested to submit to the Department within fourteen (14) days a proposed program and schedule for abatement of these violations. The Department anticipates that complete removal of hazardous wastes, the tank and appurtenances would be performed, followed by soil testing of surrounding areas to confirm an adequate clean-up. Groundwater monitoring may be a requirement if contaminants have left the site.


This letter does not waive, either expressly or by implication, the power or authority of the Commonwealth of Pennsylvania to prosecute for any and all

ORIGINAL  
(Red)



violations of law arising prior to or after the issuance of this letter or the conditions upon which the letter is based. This letter shall not be construed so as to waive or impair any rights of the Department of Environmental Resources, heretofore or hereafter existing.


This letter shall also not be construed as a final action of the Department of Environmental Resources.

If you have any questions concerning this matter, please feel free to contact me at 

Very truly yours,



MICHAEL M. BOBEE  
Waste Management Specialist



ORIGINAL  
(Red)



COMMONWEALTH OF PENNSYLVANIA  
DEPARTMENT OF ENVIRONMENTAL RESOURCES  
1875 New Hope Street  
Norristown, PA 19401  
215 270-1948

September 12, 1986

CERTIFIED MAIL NO. P041219237

Mr. Frank Bell  
[REDACTED]

Re: Gelco Facility  
714 Dunksferry Road  
Bensalem, PA 19020

Dear Mr. Bell:

In reference to my conversation of September 10, 1986 with [REDACTED] the Department understands that you have entered into a contract with OH Materials to resolve the existing waste disposal problem at the Gelco facility.

Our information is that OH Materials has suspended clean up activities due to non-payment for work performed. Be advised that unless you correct this work stoppage which we view as continued non-compliance we will consider developing an Order which will further penalize you for lack of compliance with the Department's Hazardous Waste Regulations.

You are asked to respond to this letter with a statement of your intended actions to resolve this matter within five days of receipt of this letter.

Very truly yours,

MICHAEL M. BOBEK  
Waste Management Specialist



ORIGINAL  
(Red)

R-585-3-9-13

NON-SAMPLING SITE RECONNAISSANCE SUMMARY REPORT  
GELCO TRUCK LEASING  
PREPARED UNDER

TDD NO. F3-8812-06  
EPA NO. PA-2135  
CONTRACT NO. 68-01-7346

FOR THE

HAZARDOUS SITE CONTROL DIVISION  
U.S. ENVIRONMENTAL PROTECTION AGENCY

MARCH 10, 1989

NUS CORPORATION  
SUPERFUND DIVISION

SUBMITTED BY

REVIEWED BY

APPROVED BY



ORIGINAL  
(Red)

### Scope of Work


NUS FIT 3 was tasked to conduct a non-sampling site reconnaissance of the Gelco Truck Leasing site, located on Dunks Ferry Road in Bensalem Township, Bucks County, Pennsylvania (see figure 1, page 2).

### Background Information

Gelco Truck Leasing is located in the I-95 Industrial Park. Gelco leases various types of trucks, tractor trailers, and tankers for industrial and commercial uses. Light maintenance of the trucks is performed in a garage on site. Gelco leases the site building from Frank and Doris Bell, of Beverly, New Jersey, the property owners. (The Bells are also listed as Diputs, Incorporated, a Bell Corporation, in much of the site correspondence.)

The site property is approximately one acre in size. Access to the site is via Moore Avenue and/or Dunks Ferry Road; the property is a corner lot. A chain-link fence borders the site to the west and south. Beyond the fences are residential properties. A brick building is located on the southern half of the property. The building houses an office for Rohm and Haas and the offices and a garage for Gelco. The northern half of the property is a filled, stone-covered lot used by Gelco for vehicle parking. An underground diesel fuel tank with an above-ground pump is also located in this area. Metal scraps and empty 55-gallon drums are stored behind the Gelco garage (see figure 2, page 3).


In the 1960s and early 1970s, prior to Gelco's operation, a chemical waste hauling business was operated at the site. The business was owned by Gus Propper. Mr. Propper had been involved in several instances of illegal waste disposal. In one case, Mr. Propper was convicted of dumping volatile organic wastes into the sanitary sewer system via a drain inside the on-site building.



SOURCE: (7.5 MINUTE SERIES) U.S.G.S. BEVERLY, PA - N.J. QUAD.

**SITE LOCATION MAP**  
**GELCO TRUCK LEASING, BENSALEM TWP., PA**  
 SCALE 1: 24000





SITE SKETCH  
GELCO TRUCK LEASING, BENSALEM TWP., PA  
 ( NO SCALE )

FIGURE 2



ORIGINAL  
(Red)

Gelco began leasing the property in the late 1970s. Light maintenance, including oil changes, is performed on site. Waste oil had been piped from inside the building to an outside, underground 10,000-gallon holding tank located north of the building. Spurred by several overflows of the tank, including one that had contaminated soils along the foundation of the building, Gelco removed the holding tank in May 1986. During the removal of this tank, another larger underground tank was discovered about 20 feet north of the building. This larger tank is believed to have been used as a holding tank for chemical wastes during Mr. Proper's operations. A three-inch pipe led from the tank back into the building; the inlet of the pipe is believed to have been covered with cement inside the building. The "tank" itself was not truly a tank but consisted of a series of what appeared to be truck wheel rims assembled in a vertical column to create a well. The tank, which has also been described as an old railroad tank car, contained a nine-foot column of an unidentified black and odorous liquid. A six- to seven-foot-deep pipe served as a vent to the tank. Analysis of the tank contents revealed levels of several volatile organic contaminants including xylene, toluene, and ethylbenzene.

Gelco contracted O.H. Materials (OHM), a waste removal firm, to clean up the oil spill and the buried tank and its contents. An agreement was made between Gelco and the Bells: Gelco would be responsible for the oil-contaminated soil; Frank Bell would be responsible for the removal of the tank and its contents. OHM completed the work for both parties. The contaminated soils were removed and backfilled with clean soils in September 1986. The tank and its contents, as well as excavated soils, were removed and backfilled with clean soils in March 1987. All of the clean-up work was overseen and approved by the Pennsylvania Department of Environmental Resources (PA DER). (See page 5 for details of both removals and cleanup.)

No additional regulatory or remedial work has been completed at the site since the removal of the soil and tanks. The area where the two tanks had been located is currently a stone-covered lot, level with the surrounding lot, that is used for vehicle parking. Gelco continues to lease the property from the Bells; however, an underground tank is no longer used for the holding of waste oils.



ORIGINAL  
(Red)

### Sampling to Date

In the past, there had been several overflows of the outside, underground tank used by Gelco for the storage of waste oil. Oil had begun to collect and pool against the foundation of the building. This prompted Gelco to have the oil-contaminated soil and the tank removed. During the tank's removal, a second tank was discovered. OHM, of Windsor, New Jersey, a waste removal firm, was contracted by Gelco to sample, analyze, and clean up the two tank areas.

On May 14, 1986, OHM collected samples of the waste oil tank area soils, the contents of the second tank, and the waste oil from the removed oil holding tank. The samples were analyzed by Wastex Industries, Incorporated, of Pottstown, Pennsylvania, for metals, pesticides, base/neutral fractions, acid extractables, and volatile organics. Only the second tank's contents exhibited any notable contamination. Several volatile organic contaminants were detected in the tank sample, including total xylenes (73 mg/kg), toluene (24 mg/kg), ethylbenzene (7.8 mg/kg), 1,1,2,2-tetrachloroethane (1.4 mg/kg), 1,1,1-trichloroethane (0.7 mg/kg), and benzene (0.6 mg/kg). (See attachment 2 for sample data.)

On May 21, 1986, the Bells, as owners of the Gelco property, were notified by PA DER of the existing situation at the site. PA DER suggested that the Bells work with Gelco in the removal and clean-up effort. In addition, as the property owners, the Bells were required by PA DER to provide a proposal to correct the disposal violations at the site. The proposal had to identify the following: the method of collection, transportation, and disposal of contaminants; the procedures to determine the source of contaminants; the method to render the well and piping system useless; and the monitoring well locations, with a design and protocol to establish a monitoring program that would determine the extent of contamination and the potential for remediation. (Not all of these conditions have been met at the site, although removal has been completed.)

Frank Bell and representatives from the Bucks County Health Department, Gelco Corporation, OHM, and PA DER met on May 30, 1986 to discuss the Gelco cleanup. The samples collected in early May showed that the contents of the second tank (referred to as a sump) and the oil and soil were hazardous. Gelco agreed to take responsibility for the oil/soil removal, and Frank Bell agreed to be responsible for the sump contents. OHM would be the consultant for both parties. Work was scheduled to begin on June 3, 1986.

A work proposal was submitted to Gelco and Mr. Bell by OHM on June 4, 1986. OHM planned, in summation, to excavate all visually contaminated soils on the surface and subsurface, pump the sump contents into 55-gallon drums, properly stage all excavated materials, and provide clean soil for backfill. Upon completion of these tasks, OHM would again meet with site representatives to determine the best remedial approach. The waste oil was analyzed and approved for incineration by Caldwell Systems, Incorporated at its facility in Lenoir, North Carolina (see attachment 2 for data).

On September 30, 1986, OHM completed the soil excavation for the Gelco portion of the work order. Oil-contaminated soils were removed to a depth where analysis of the soil contained less than 100 ppm hydrocarbons. The pit was then backfilled with clean soil. The removed soil/waste material was transported to Waste Conversions, Incorporated's facility in Hatfield, Pennsylvania. Work was scheduled to begin on October 27, 1986 for the removal of the tank. The removal was delayed due to a backlog at the incinerator, which was scheduled to receive the drums of liquid waste. The remaining nonpumpable tank sludge would be solidified with kiln dust and hauled by Waste Conversions to a secure landfill in Michigan. According to Kevin Wood, of OHM, Bell would cut up and dispose the excavated tank and backfill the pit. Upon extraction of the tank, soil samples would be collected by OHM.

Removal of the second tank and the excavated soil was completed by March 4, 1987. The dismantled tank was taken to Delaware Valley Scrap Yard. Soil waste was taken by Delvecchio Waste Haulers to Waste Conversions. A composite soil sample of five locations surrounding the pit was taken after the tank removal and analyzed by Century Laboratories, Incorporated, of Thorofare, New Jersey. Toluene (11 ug/kg) was detected in the soil sample. PA DER did not feel this was a threat to groundwater and allowed the backfill of the Bell excavation. The Gelco/Bell cleanup was completed in April 1987.

In a related, although unconnected matter, PA DER collected soil samples for an investigation of the adjacent Dorsey property in 1984 and 1985. The Dorsey property, a private lot located directly behind the Gelco facility, had suspected soil contamination. PA DER was asked to inspect the property due to observed stressed vegetation and an uneven ground surface with some sinking in spots. Gelco was identified, along with two other industries, as a possible source. No significant contamination was detected. (See attachment 3 for sample data.)

ORIGINAL  
(Red)

### Geology Information

The Gelco Truck Leasing site lies within the Atlantic Coastal Plain Province of southeastern Pennsylvania.<sup>1</sup> The geologic framework of the Coastal Plain Province consists of underlying, gently southeastward-dipping, unconsolidated marine and fluvial deposits of clay, silt, sand, and gravel of Late Cretaceous and Tertiary age. Areas are also covered by interglacial fluvial deposits of Quaternary (Pleistocene) age. The land surface has a very gentle slope and dendritic drainage pattern.<sup>2</sup>

The site is immediately underlain by the Quaternary age Trenton Gravel.<sup>3</sup> The Trenton Gravel is a gray to pale reddish-brown, medium- to coarse-grained, very gravelly sand. There are also interbedded clay-silt and crossbedded sand layers.<sup>1,2,4</sup> The formation is most continuous and occurs chiefly in the lowland along the Delaware River, from Trenton to the Atlantic Ocean.<sup>2</sup> The youngest of the interglacial formations, the Trenton Gravel (the equivalent of the Cape May Formation of New Jersey) has been correlated with the Sangamon interglacial stage (approximately 300,000 years ago).<sup>2,4</sup> The Trenton Gravel was part of an estuarine-deltaic-marine depositional environment driven and supplied by meltwater and sediment derived from retreating glaciers.<sup>2</sup> Its thickness is approximately 30 to 40 feet.<sup>1,4</sup>

Underlying the Trenton Gravel throughout the three-mile radius is the Cretaceous age Potomac Group and Raritan Formation. These geologic units make up the important Potomac-Raritan-Magothy aquifer, a major water supply source for residents of New Jersey. In the Delaware Valley, Raritan age sediments are indistinguishable from the underlying Potomac Group.<sup>5</sup> The aquifer has been subdivided into the following units: upper clay, upper sand (formerly the Old Bridge Sand), middle clay, middle sand (formerly the Sayreville Sand), lower clay, and lower sand (formerly the Farrington Sand).<sup>5,6</sup> Some authors believe that the Old Bridge Sand Member should be assigned to the Magothy Formation (which overlies the Raritan in New Jersey). This suggests that the Potomac Group and the Raritan and Magothy Formations would function as one hydrologic unit in the Southern Coastal Plain of New Jersey.<sup>6</sup>

The upper clay of the Potomac-Raritan-Magothy aquifer is chiefly red, white, gray, and yellow clay and has a maximum thickness of 35 feet. The upper sand is a medium- to coarse-grained sand with minor amounts of very fine- to fine-grained sand. This sand has a thickness of 35 to 55 feet and commonly forms a single, unconfined aquifer with the overlying Trenton Gravel.<sup>1</sup>

The middle clay unit consists of red and white clay and is commonly about 20 feet thick. The middle sand unit is chiefly a brown, yellow, white, and gray, coarse-grained sand and gravel with a maximum thickness of 25 feet.<sup>1</sup>

The lower clay unit consists of brick red and gray clay that is approximately 25 to 40 feet thick.<sup>1,6</sup> Often, when the middle sand unit is absent, the lower and middle clay units merge to form a thick (47 to 60 feet) confining bed. The lower sand unit consists of coarse-grained sand and fine gravel that grade upward into medium- to fine-grained sand containing a few beds of white clay. The lower sand can range in thickness from 11 to 120 feet.<sup>1,6</sup>

The site is underlain by an Urban land - Howell Complex soil. Urban structures cover so much of this land type that identification of the soils is not practical. Most areas have been smoothed, and the original soil material has been disturbed, filled over, or otherwise destroyed by construction.<sup>7</sup>



ORIGINAL  
(Red)

### Summary of Activities

On Thursday, January 5, 1989, NUS FIT 3 personnel [REDACTED] conducted a non-sampling site reconnaissance of the Gelco Truck Leasing site. FIT 3 was accompanied on site by Frank Bell, the property owner. Weather conditions during the site visit were partly cloudy and windy. The temperature was 18°F, with a significant wind chill. Photographs were taken on site (see attachment 1).

### Persons Contacted

#### **Prior to Field Trip**

Robert Allen  
PA DER  
Norristown Regional Office  
1875 New Hope Street  
Norristown, PA 19401  
(215) 270-1948



Doris Bell  
Property Owner  
P.O. Box 352  
Beverly, NJ 08010  
(609) 386-7535

Karen Graham  
Site Investigation Officer  
U.S. EPA, Region III  
841 Chestnut Building  
Ninth and Chestnut Streets  
Philadelphia, PA 19107  
(215) 597-2317

#### **At the Site**

Frank Bell  
Property Owner  
[REDACTED]  
[REDACTED]

#### **Post Site Visit**

Karen Graham  
Site Investigation Officer  
U.S. EPA, Region III  
841 Chestnut Building  
Ninth and Chestnut Streets  
Philadelphia, PA 19107  
(215) 597-2317

ORIGINAL  
(Red)

Site Observations

- The HNU background reading was 1.2 ppm; no readings above background were recorded during on-site activities.
- The mini-alert setting was on the X1 position; no readings above background were recorded.
- The subject site is located in an industrial park off Interstate 95.
- The property was occupied by one brick building, which housed Gelco Truck Leasing and Rohm and Haas offices.
- A large concrete pad extended northwardly from the entrance to Gelco's facility to a diesel fuel pumping station.
- An open, stone-covered lot was used for parking Gelco's trucks.
- The area where two underground tanks had been removed was level and stone covered. No stains were observed.
- A hole in the northern facade of Gelco's building, located two to three inches above the ground surface, had been "plugged" with stones.
- Empty drums and scraps had been stored behind the Gelco building.
- A five-feet-high fence followed the southern and western borders of the property.
- Residential homes were located south and west of the Gelco property.
- No surface stains or odors were observed on site.

ORIGINAL  
(Red)

**Geology and Groundwater References**

1. Greenman, D.W., D.R. Rima, W.N. Lockwood, and H. Meisler, Pennsylvania Geological Survey. Groundwater Resources of the Coastal Plain Area of Southeastern Pennsylvania. Bulletin W13, 1961.
2. Wolfe, Peter E. Landscapes of the Coastal Plain. In The Geology and Landscapes of New Jersey. New York: Crane, Russak and Company. 1977.
3. Pennsylvania Department of Environmental Resources, Bureau of Topographic and Geological Survey. Atlas of Preliminary Geological Quadrangle Maps of Pennsylvania. Beverly, Camden, and Frankford Pennsylvania Quadrangles. 1981.
4. Pennsylvania Department of Environmental Resources, Bureau of Topographic and Geological Survey. Engineering Characteristics of the Rocks of Pennsylvania. Environmental Geology Report 1, 1982.
5. Paulachok, Gary N., et al., United States Geological Survey. Hydrologic Data for Aquifers in Philadelphia, Pennsylvania. Open-File Report 83-149, 1984.
6. Zapecza, Otta S., United States Geological Survey. Hydrogeologic Framework of the New Jersey Coastal Plain. Open-File Report 84-730, 1984.
7. United States Department of Agriculture, Soil Conservation Service. Soil Survey of Bucks and Philadelphia Counties, Pennsylvania. 1975.



ORIGINAL  
(Red)

ATTACHMENT 1






PHOTO LOCATION MAP  
GELCO TRUCK LEASING, BENSALEM TWP., PA  
( NO SCALE )

ORIGINAL  
(Red)

ATTACHMENT 2



28 S HANOVER STREET, POTTSVILLE, PA 19464 215 / 327-0880  
125 MAIN AVENUE, ELMWOOD PARK, N.J. 07407 201 / 791-6700

May 20, 1986

for **O. H. Materials Co.**  
**P.O. Box 41**  
**Windsor, NJ 08561-0041**  
**Attn: Kevin Wood**

P.O. # **J 3814-59642** Proj. # **3814**

Identification of Samples **Ben Salem, PA Gelco**

1. **05-1686-17 3814-#01 Oil**

2. **05-1686-18 3814-#02 Sump**

3. **05-1686-19 3814-#03 Soil**

4. \_\_\_\_\_

Site Sampled **5-14-86** Time **1:30** Date Rec. **5-16-86** Time **10:00**

Sampled By **ME** Rec. by **MDD**

Date Complete: \_\_\_\_\_

Tested By: **Wastex**

Class of Sample: ☐ Grab ☐ Grab Composite ☐ Continuous

**OIL SUMP SOIL**

Analysis	#1	#2	#3	#4	Analysis	#1	#2	#3
BOD (5 day 20 C) mg/l					<b>Leachate</b>			
COD mg/l					<b>METALS</b>			
Dissolved Oxygen mg/l					Aluminum mg/l			
DO mg/l					Antimony mg/l			
Relative Stability				X	Arsenic mg/l	< 0.001	< 0.001	< 0.001
Acidity mg/l CaCO <sub>3</sub>				X	Barium mg/l	< 0.1	< 0.1	< 0.1
Alkalinity mg/l CaCO <sub>3</sub>					Beryllium mg/l			
Hardness mg/l CaCO <sub>3</sub>				X	Cadmium mg/l	< 0.005	< 0.010	< 0.010
pH					Calcium mg/l			
Spec Cond $\mu$ mhos/cm				X	Chromium mg/l	< 0.05	< 0.05	< 0.05
Specific Gravity					Chromium (Hex) mg/l			
Color Pt-Co					Copper mg/l			
Odor TON					Iron mg/l			
Turbidity NTU				X	Lead mg/l	< 0.05	< 0.05	< 0.05
Bromide mg/l					Magnesium mg/l			
Chloride mg/l					Manganese mg/l			
Chlorine-Residual mg/l				X	Mercury mg/l	< 0.0002	< 0.0002	< 0.0002
Cyanide mg/l					Nickel mg/l			
Fluoride mg/l					Potassium mg/l			
Ammonia Nitrogen mg/l				X	Selenium mg/l	< 0.002	< 0.002	< 0.002
Nitrate Nitrogen mg/l				X	Silver mg/l	< 0.01	< 0.01	< 0.01
Nitrite Nitrogen mg/l					Sodium mg/l			
Organic Nitrogen mg/l					Titanium mg/l			
Total Phosphate as P mg/l					Tin mg/l			
Orthophosphate as P mg/l					Zinc mg/l			
Silica mg/l								
Sulfate mg/l								
Sulfide mg/l								
Sulfite mg/l								
Total Solids mg/l					X <b>Petroleum</b>			
Dissolved Solids mg/l					<b>Hydrocarbons</b>	<b>64.5%</b>		
Suspended Solids mg/l								
Volatile Solids mg/l								
Settleable Solids mg/l								
Grease and Oil mg/l								
Detergents mg/l								
Phenols mg/l								

**BACTERIOLOGICAL**

St. Plate Count No./ml				
Total Coliform No./100ml				
Fecal Coliform No./100ml				

Signature

[Redacted Signature]



WASTEX  
INDUSTRIES, INC.

28 S. Hanover Street  
Pottstown, PA 19464  
215/327-0880

EPA 38-005  
NJDEP 77371

Licensed Analytical Laboratories



P.O. Box 360  
125 Main Ave.  
Elmwood Park, N.J. 07407  
201/791-6700

## NOTES AND COMMENTS

-----

### VALUE

If the result is a value greater than or equal to the detection limit, report the value.

U

Compound was analyzed for but Not Detected.  
The number is the minimum attainable detection limit for the sample.

B

This flag is used when the analyte is found in the blank as well as a sample. It indicates possible/probable contamination and warns the data user to take appropriate action.

D

Compound was detected but less than the minimum detection limit.

\*\*

Anthracene coelutes with phenanthrene and is quantitated as all phenanthrene.


\*\*\*

Benzo (b) fluoranthene and Benzo (k) fluoroanthene coelute and are quantitated as all Benzo (k) fluoranthene.

\*\*\*\*

Chrysene coelutes with Benzo (a) anthracene and is quantitated as all Benzo (a) anthracene.

Cis-1,2-Dichloroethene (a non-targetted compound) coelutes with Transl, 2-Dichloroethene and the MS cannot distinguish one from the other.





28 S. Hanover Street  
Pottstown, PA 19464  
215/327-0880

SOILS  
AT OIL TANK AREA

EPA 38-005  
NJDEP 77371

Licensed Analytical Laboratories



P.O. Box 360  
125 Main Ave.  
Elmwood Park, N.J. 07407  
201/791-6700

O. H. Materials Co.  
P.O. Box 41  
Windsor, NJ 08561-0041  
Attn: Kevin Wood

Date Sampled: 5-14-86 Time: 1:30  
Date Received: 5-16-86 Time: 10:00  
Sampled By: ME  
Received By: MDD  
Date Completed:  
Tested By: Wastex  
P. O.: J3814-59642  
LAB #: 05-1686-19 Soil  
Sample I.D. 3814-#03 Ben Salem, PA  
Gelco

#### PESTICIDES

PARAMETERS	RESULTS mg/kg
1P. Aldrin	<0.10
2P. alpha-BHC	<0.10
3P. beta-BHC	<0.10
4P. gamma-BHC	<0.10
5P. delta-BHC	<0.10
6P. Chlordane	<0.10
7P. 4,4'-DDT	<0.10
8P. 4,4'-DDE	<0.10
9P. 4,4'-DDD	<0.10
10P. Dieldrin	<0.10
11P. alpha-Endosulfan	<0.10
12P. beta-Endosulfan	<0.10
13P. Endosulfan Sulfate	<0.10
14P. Endrin	<0.10
15P. Endrin Aldehyde	<0.10
16P. Heptachlor	<0.10
17P. Heptachlor Epoxide	<0.10

PARAMETERS	RESULTS mg/kg
18P. PCB-1242	<0.50
19P. PCB-1254	<0.50
20P. PCB-1221	<0.50
21P. PCB-1232	<0.50
22P. PCB-1248	<0.50
23P. PCB-1260	<0.50
24P. PCB-1016	<0.50
25P. Toxaphene	<2.00

DIOXIN

PARAMETER	RESULT
2,3,7,8-Tetrachlorodibenzo-P-Dioxin	*

NA - Not Applicable as per U.S.E.P.A. NPDES Form 2-C, Table 2C-2.

\* - This parameter is not analyzed by Wastex Industries, Inc. due to its high risk toxicity. This analysis is available through a Wastex subcontractor.

Respectfully submitted,



CLIENT I.D.: Ben Salem, PA Gelco

FRN NO.: &gt;A0011 /&gt;B0052

Oil Tank

PARAMETER	RESULTS mg/kg	PARAMETER	RESULTS mg
<u>ACID EXTRACTABLES</u>		<u>BASE/NEUTRAL FRACTION</u>	
2-Chlorophenol	2.5U	Hexachlorobenzene	1.U
4-Chloro-3-methylphenol	2.5U	Hexachlorobutadiene	1.U
2,4-Dichlorophenol	2.5U	Hexachlorocyclopentadiene	1.U
2,4-Dimethylphenol	2.5U	Hexachloroethane	5.U
2,4-Dinitrophenol	25.U	Indeno(1,2,3-c,d)pyrene	1.U
4,6-Dinitro-2-methylphenol	2.5U	Isophorone	1.U
2-Nitrophenol	2.5U	Naphthalene	2.D
4-Nitrophenol	2.5U	Nitrobenzene	1.U
Pentachlorophenol	2.5U	N-Nitrosodimethylamine	1.U
Phenol	2.5U	N-Nitrosodiphenylamine	1.U
2,4,6-Trichlorophenol	2.5U	N-Nitrosodipropylamine	1.U
		Phenanthrene	8.
		Pyrene	16.
		1,2,3-Trichlorobenzene	1.U
<u>BASE/NEUTRAL FRACTION</u>		<u>VOLATILE FRACTION</u>	
Acenaphthene	1.	Benzene	0.5U
Acenaphthylene	1.	Bromodichloromethane	0.5U
Anthracene	**	Bromoform	0.5U
Benzidine	5.U	Bromomethane	0.5U
Benz(a)anthracene	7.	Carbon tetrachloride	0.5U
Benzo(b)fluoranthene	***	Chlorobenzene	0.5U
Benzo(k)fluoranthene	3.	Chlorodibromomethane	0.5U
Benzo(g,h,i)perylene	2.D	Chloroethane	0.5U
Benzo(a)pyrene	4	2-Chloroethyl vinyl ether	0.5U
Benzyl butyl phthalate	1.U	Chloroform	1.B
4-Bromophenyl phenyl ether	1.U	Chloromethane	0.5U
bis(2-Chloroethyl)ether	1.U	1,1-Dichloroethane	0.5U
bis(2-Chloroethoxy)ether	1.U	1,2-Dichloroethane	0.5U
bis(2-Chloroisopropyl)ether	1.U	1,1-Dichloroethene	0.5U
2-Chloronaphthalene	1.U	trans-1,2-Dichloroethene	0.5U
4-Chlorophenyl phenyl ether	1.U	1,2-Dichloropropane	0.5U
Chrysene	***	cis-1,3-Dichloropropene	0.5U
Dibenzo(a,h)anthracene	4.U	trans-1,3-Dichloropropene	0.5U
Di-n-butyl phthalate	1.U	Ethylbenzene	0.5U
1,2-Dichlorobenzene	1.U	Fluorotrichloromethane	0.5U
1,3-Dichlorobenzene	1.U	Methylene Chloride	34.B
1,4-Dichlorobenzene	1.U	1,1,2,2-Tetrachloroethane	0.5U
3,3'-Dichlorobenzidine	1.U	Tetrachloroethene	0.5U
Diethyl phthalate	2.5U	Toluene	0.8
Dimethyl phthalate	1.U	1,1,1-Trichloroethane	0.5U
2,4-Dinitrotoluene	1.U	1,1,2-Trichloroethane	0.5U
2,6-Dinitrotoluene	1.U	Trichloroethene	0.5U
Di-n-octyl phthalate	1.U	Vinyl Chloride	0.5U
1,2-Diphenylhydrazine	1.U	Total Xylenes	0.5U
bis(2-ethylhexyl)phthalate	9.		
Fluoranthene	21.		
Fluorene	1.U		

CLIENT: Q. H. Materials

SAMPLE I.D.: 05-1686-19 <sup>ORIGINAL</sup>

CLIENT I.D.: Ben Salem, PA Gelco

FRN NO.: >A0011/>B0052

PARAMETER RESULTS mg/kg

PESTICIDE/PCB FRACTION

Aldrin	1.U
a-BHC	1.U
b-BHC	1.U
d-BHC	1.U
g-BHC	1.U
Chlordane	5.U
4,4'-DDD	1.U
4,4'-DDE	1.U
4,4'-DDT	1.U
Dieldrin	1.U
a-Endosulfan	1.U
b-Endosulfan	1.U
Endosulfan sulfate	1.U

PARAMETER RESULTS mg/k


PESTICIDE/PCB FRACTION

Endrin	1.U
Endrin aldehyde	1.U
Heptachlor	1.U
Heptachlor epoxide	1.U
Toxaphene	5.U
PCB-1242	5.U
PCB-1254	5.U
PCB-1221	5.U
PCB-1232	5.U
PCB-1248	5.U
PCB-1260	5.U
PCB-1016	5.U



TOTAL ION CHROMATOGRAM

File NA0011 47.0-450.0 amu. 051686-19 506:10ML 051886 17:25  
TIC



Data File: NA0011::D1

Name: 051686-19 506:10ML

Misc: 051886 17:25

26000V A/D=203 T=60 DB-5

Id File: IDBNA0::90

Title: CLP BNA EXTRACTABLES

Last Calibration: 860518 14:42


Operator ID: DT9093

Quant Time: 860518 18:19

Injected at: 860518 17:24

Original  
Page

TOTAL ION CHROMATOGRAM



Data File: >B0052::D1

Name: 051686-19,16/10ML,B

Nisc: 052286 21:00 E=1900,A/D=2^5,T=40,SP=1000,5+5UL(1S+SS)

Id File: IDVOL::M1

Title: EPA METHOD 624 VOLATILES

Last Calibration: 860522 14:47

Operator ID: MOLE

Quant Time: 860522 22:08

Injected at: 860522 21:06



WASTEX  
INDUSTRIES, INC.

28 S. Hanover Street  
Pottstown, PA 19464  
215/327-0880

SUMP

EPA 38-005  
NJDEP 77371

Licensed Analytical Laboratories



P.O. Box 360  
125 Main Ave.  
Elmwood Park, N.J. 07407  
201/791-6700

O. H. Materials Co.  
P.O. Box 41  
Windsor, NJ 08561-0041  
Attn: Kevin Wood

Date Sampled: 5-14-86 Time: 1:30  
Date Received: 5-16-86 Time: 10:00  
Sampled By: ME  
Received By: MDD  
Date Completed: \_\_\_\_\_  
Tested By: Wastex  
P. O.: J3814-59642  
LAB #: 05-1686-18 *Sump*  
Sample I.D. 3814-#02 Ben Salem, PA  
Gelco

PESTICIDES

PARAMETERS	RESULTS mg/kg
1P. Aldrin	<0.20
2P. alpha-BHC	<0.20
3P. beta-BHC	<0.20
4P. gamma-BHC	<0.20
5P. delta-BHC	<0.20
6P. Chlordane	<0.20
7P. 4,4'-DDT	<0.20
8P. 4,4'-DDE	<0.20
9P. 4,4'-DDD	<0.20
10P. Dieldrin	<0.20
11P. alpha-Endosulfan	<0.20
12P. beta-Endosulfan	<0.20
13P. Endosulfan Sulfate	<0.20
14P. Endrin	<0.20
15P. Endrin Aldehyde	<0.20
16P. Heptachlor	<0.20
17P. Heptachlor Epoxide	<0.20

ORIGINAL

(7ed)

Page 2  
# 05-1686-18  
Pesticides

PARAMETERS	RESULTS mg/kg
18P. PCB-1242	< 0.50
19P. PCB-1254	< 0.50
20P. PCB-1221	< 0.50
21P. PCB-1232	< 0.50
22P. PCB-1248	< 0.50
23P. PCB-1260	< 0.50
24P. PCB-1016	< 0.50
25P. Toxaphene	< 2.00


## DIOXIN

PARAMETER	RESULT
2,3,7,8-Tetrachlorodibenzo-P-Dioxin	*

NA - Not Applicable as per U.S.E.P.A. NPDES Form 2-C, Table 2C-2.

\* - This parameter is not analyzed by Wastex Industries, Inc. due to its high risk toxicity. This analysis is available through a Wastex subcontractor.

Respectfully submitted,

  
Director

CLIENT I.D.: Ben Salem, PA Gelco

FRN NO.: &gt;A0011/&gt;B0053

ORIGINAL  
(Red)

PARAMETER	RESULTS mg/kg	PARAMETER	RESULTS mg
<u>ACID EXTRACTABLES</u>		<u>BASE/NEUTRAL FRACTION</u>	
2-Chlorophenol	50.U	Hexachlorobenzene	20.U
4-Chloro-3-methylphenol	50.U	Hexachlorobutadiene	20.U
2,4-Dichlorophenol	50.U	Hexachlorocyclopentadiene	100.U
2,4-Dimethylphenol	50.U	Hexachloroethane	20.U
2,4-Dinitrophenol	500.U	Indeno(1,2,3-c,d)pyrene	80.U
4,6-Dinitro-2-methylphenol	50.U	Isophorone	20.U
2-Nitrophenol	50.U	Naphthalene	20.U
4-Nitrophenol	50.U	Nitrobenzene	20.U
Pentachlorophenol	50.U	N-Nitrosodimethylamine	20.U
Phenol	50.U	N-Nitrosodiphenylamine	20.U
2,4,6-Trichlorophenol	50.U	N-Nitrosodipropylamine	20.U
		Phenanthrene	20.U
		Pyrene	20.U
		1,2,3-Trichlorobenzene	20.U
<u>BASE/NEUTRAL FRACTION</u>		<u>VOLATILE FRACTION</u>	
Acenaphthene	20.U	Benzene	0.6
Acenaphthylene	20.U	Bromodichloromethane	0.5U
Anthracene	**	Bromoform	0.5U
Benzidine	100.U	Bromomethane	0.5U
Benz(a)anthracene	20.U	Carbon tetrachloride	0.5U
Benzo(b)fluoranthene	***	Chlorobenzene	0.5U
Benzo(k)fluoranthene	20.U	Chlorodibromomethane	0.5U
Benzo(g,h,i)perylene	80.U	Chloroethane	0.5U
Benzo(a)pyrene	20.U	2-Chloroethyl vinyl ether	0.5U
Benzyl butyl phthalate	20.U	Chloroform	1.2B
4-Bromophenyl phenyl ether	20.U	Chloromethane	0.5U
bis(2-Chloroethyl)ether	20.U	1,1-Dichloroethane	0.5U
bis(2-Chloroethoxy)ether	20.U	1,2-Dichloroethane	0.5U
bis(2-Chloroisopropyl)ether	20.U	1,1-Dichloroethene	0.5U
2-Chloronaphthalene	20.U	trans-1,2-Dichloroethene	0.5U
4-Chlorophenyl phenyl ether	20.U	1,2-Dichloropropane	0.5U
Chrysene	***	cis-1,3-Dichloropropene	0.5U
Dibenzo(a,h)anthracene	80.U	trans-1,3-Dichloropropene	0.5U
Di-n-butyl phthalate	20.U	Ethylbenzene	7.8
1,2-Dichlorobenzene	20.U	Fluorotrichloromethane	0.5U
1,3-Dichlorobenzene	20.U	Methylene Chloride	29.8
1,4-Dichlorobenzene	20.U	1,1,2,2-Tetrachloroethane	1.4
3,3'-Dichlorobenzidine	50.U	Tetrachloroethene	0.5U
Diethyl phthalate	20.U	Toluene	24.
Dimethyl phthalate	20.U	1,1,1-Trichloroethane	0.7
2,4-Dinitrotoluene	20.U	1,1,2-Trichloroethane	0.5U
2,6-Dinitrotoluene	20.U	Trichloroethene	0.5U
Di-n-octyl phthalate	20.U	Vinyl Chloride	0.5U
1,2-Diphenylhydrazine	20.U		
bis(2-ethylhexyl)phthalate	20.U		
Fluoranthene	20.U		
Fluorene	20.U		
		Total Xylenes	73.

CLIENT: O. H. Materials

SAMPLE I.D.: 05-1686-18 *PCB/Mg*

CLIENT I.D.: Ben Salem, PA Gelco

FRN NO.: >A0011/>B0053 *(Red)*

PARAMETER RESULTS mg/kg

PESTICIDE/PCB FRACTION

Aldrin	20.U
a-BHC	20.U
b-BHC	20.U
d-BHC	20.U
g-BHC	20.U
Chlordane	100.U
4,4'-DDD	20.U
4,4'-DDE	20.U
4,4'-DDT	20.U
Dieldrin	20.U
a-Endosulfan	20.U
b-Endosulfan	20.U
Endosulfan sulfate	20.U


PARAMETER RESULTS mg/l

PESTICIDE/PCB FRACTION

Endrin	20.U
Endrin aldehyde	20.U
Heptachlor	20.u
Heptachlor epoxide	20.u
Toxaphene	100.U
PCB-1242	100.U
PCB-1254	100.U
PCB-1221	100.U
PCB-1232	100.U
PCB-1248	100.U
PCB-1260	100.U
PCB-1016	100.U

ORIGINAL  
(Rev)

TOTAL ION CHROMATOGRAM



Data File: B0053::D1

Name: 051686-18,16/10ML,B

Misc: 052286 22:10 E=1900,A/D=2^5,T=40,SP=1000,5+5UL(1S+5S)

Id File: IDVOL::M1

Title: EPA METHOD 624 VOLATILES

Last Calibration: 860522 14:47

Operator ID: MOLE

Quant Time: 860522 23:31

Injected at: 860522 22:14

ORIGINAL  
(Red)

\* \* \*  
\* C S I \*  
\* \* \*

Caldwell Systems, Inc.

Phone: (704) 728-3251 \* Lenoir, N.C. 28645

Date Arrived: 7-02-86 Sample #: CSI-922

Company: OH Materials; Frank Bell Windsor, NJ

Description: Waste Oil

WASTE SAMPLE PROFILE DATA:

Specific Gravity: 1.010 % Ash: Little Expected

Flash Point: < 140°F Chlorine: 3320 ppm

pH Value: 4.8 Sulfur: 300 ppm

BTU Value: 5880 BTU/lb

WASTE SAMPLE METALS PROFILE DATA (ppm):

Arsenic (As): < 1 Chromium (Cr): 0.7

Beryllium (Be): < 0.1 Lead (Pb): 1.2

Cadmium (Cd): 0.1 Mercury (Hg): < 1

This testing was performed in order to assure CSI/MSI that the waste in question meets the element limit levels setup by the EPA in order to remain in compliance with environmental standards.

Date of Analysis Completion: 7-02-86

Signature of Chemist: [Redacted]

Comments:

No ash test could be performed due to the fact that no muffle furnace was available at the time of testing.



File: DUCKS.

Gelco.

COMMONWEALTH OF PENNSYLVANIA  
Environmental Resources  
September 30, 1986  
8-354-1948

SUBJECT: Gelco Truck Leasing, Frank Bell Property  
714 Dunksferry Road  
Bensalem, PA

TO: GEORGE DANYLIW  
Operations Field Supervisor

FROM: 

I spoke with Kevin Wood of OH Materials on September 24, 1986 at 2:30 P.M.. He told me that the earliest OH Materials can continue clean up work at Gelco is October 27, 1986 because they have an October 29, 1986 acceptance date by Caldwell Systems, Inc. incinerator in Lenoir, North Carolina. The sludge material in that tank will be hauled by Waste Conversions to secure landfill in Michigan. According to Kevin Wood, Frank Bell will perform the following work: Cut-up and disposal of empty excavated tank and backfilling of tank pit. Kevin Wood indicated that upon extraction of the tank from the ground they will conduct sampling of the soils. He was asked to provide by Wednesday of next week copy of the TSD authorization and the sampling plan and work scope narrative. Regarding the Gelco portion of the clean up, namely the clean-up of oil contaminated soils, OH Materials excavated the soils around the waste oil tank, sampled the soils and found levels in excess of 100 ppm hydrocarbons, they excavated an additional six to eight inches of soil, resampled and determined hydrocarbon content to be below 100 ppm. Based on that level they then backfilled the site with clean soil. The contaminated soils went to Waste Conversion.

I asked Kevin Wood to provide a copy of the manifest and sampling results of that work on the Gelco portion of the property.

cc: Sarah Ginzler  
Bucks County Health Department  
Re 30 5W269.3

ORIGINAL  
(Box)

CENTURY LABORATORIES, INC.  
CLIENT: Frank Bell  
CLIENT I.D.: 714 Dunk's Ferry Rd. Bensalem, Pa.

REPORT NO: F0351  
DATE: 03/02/87

<u>PARAMETER</u>	<u>RESULTS (ug/kg)</u>
Chloromethane	10 U
Bromomethane	10 U
Vinyl Chloride	10 U
Chloroethane	10 U
Methylene chloride	3 U
1,1-Dichloroethene	3 U
1,1-Dichloroethane	5 U
trans-1,2-Dichloroethene	2 U
Chloroform	2 U
1,2-Dichloroethane	3 U
1,1,1-Trichloroethane	4 U
Carbon tetrachloride	3 U
Bromodichloromethane	2 U
1,2-Dichloropropane	6 U
trans-1,3-Dichloropropene	5 U
Trichloroethene	2 U
Benzene	4 U
Chlorodibromomethane	3 U
1,1,2-Trichloroethane	5 U
2-Chloroethyl vinyl ether	10 U
cis-1,3-Dichloropropene	5 U
Bromoform	5 U
1,1,2,2-Tetrachloroethane	7 U
Tetrachloroethene	4 U
Toluene	11
Chlorobenzene	6 U
Ethylbenzene	4 J
1,3-Dichlorobenzene	5 U
1,2+1,4-Dichlorobenzenes	10 U

DEFINITIONS:

VALUE	If the result is a value greater than or equal to the detection limit, report the value.
U	Compound was analyzed for but not detected. The number is the minimum attainable detection limit for the sample.
J	Indicates an estimated value. Mass spectral data indicates the presence of the compound at levels less than the specified detection limit.

ORIGINAL  
FILED  
Environmental Resources  
March 17, 1987  
8-354-1948

Gelco Clean-Up

[REDACTED]

[REDACTED]

The composited sample of soils taken from the tank excavation area shows 11 ug/kg of toluene in a volatile scan. I have no objection to backfilling the excavation if this sample is representative. The actual value of toluene in one area may be somewhat higher. It appears that the vast majority of contamination has been removed. As there are no firm regulations governing soil contamination, I have to rely on the soils' subsequent (or potential) contamination of groundwater. 11 ppb of toluene in soils would not threaten groundwater above any level of concern now regulated.

Re 30 3W76.1

file ✓

ORIGINAL  
(Red)

ATTACHMENT 3

**RECEIVED**  
NORRISTOWN

MAR 15 1985

ORIGINAL  
(Red)

Reply to:

- ☐ 2164 Almshouse Road  
P.O. Box 119  
Jamison, PA 18929  
Tel.: (215) 343-2056
- ☐ 930 Oak Terrace  
Southampton, PA 18966  
Tel.: (215) 364-0987

March 13, 1985

Mr. Robert Allen  
Bureau of Solid Waste Management  
Pa. Department of Environmental Resources  
1875 New Hope Street  
Norristown, Pa. 19401



Dear Bob:

On March 8 I received a letter from the Dorseys' Attorney authorizing me to release the information in my files pertaining to the above referenced project.

Enclosed, therefore, please find copies of tabulated chemical data as submitted by analytical laboratory.



Enclosures



QC Inc  
QUALITY CONTROL LABORATORY

1205 INDUSTRIAL HIGHWAY • P.O. BOX 514  
SOUTHAMPTON, PA. 18966 • 215/355-3800

ORIGINAL  
(Red)

MERCURI & ASSOCIATES

P.O. BOX 119

JAMISON, PA

18929

ATTN: JOSEPH A. PALERMO, JR.

REPORT DATE :11/14/84

SAMPLE DATE :10/16/84

SAMPLE TIME :10:00AM

SAMPLE TEMP :NA F

SAMPLED BY :CJ

COLLECTED BY :CJ

ANALYSIS DATE:10/17/84

SAMPLE/CONTAINER	TEST NUMBER —>	WD203-MGK	WD204-MGK	WD207-MGK	WD209-MGK	WD214-MGK	WD217-MGK	WD221-MGK	WD222-MGK		
	TEST NAME —>	ARSENIC	BARIUM	CADMIUM	CHROMIUM	LEAD	MERCURY	SELENIUM	SILVER		
	UNIT MEASURE —>	MG/KG	MG/KG	MG/KG	MG/KG	MG/KG	MG/KG	MG/KG	MG/KG		
HG-84-0387		9.2	128.	5.0	41.9	417.	0.15	<0.01	2.1		
044539 QC SUPPLIED CONTAINER											

SAMPLE# COMMENT NOTE: EACH SAMPLE ABOVE IS GIVEN A UNIQUE ID# (PRINTED JUST BELOW THE SAMPLE)

SAMPLED BY CUSTOMER

044539 QC#34087

044539 ALL TESTING IS CONDUCTED IN ACCORDANCE WITH E.P.A. METHODOLOGY.

10/16/84  
10/17/84



**QC Inc**  
QUALITY CONTROL LABORATORY

1205 INDUSTRIAL HIGHWAY • P.O. BOX 514 • SOUTHAMPTON, PA 18966-0514 • (215) 355-3900

ORIGINAL  
(Red)

MAR 1 1985

Mercuri & Associates  
Re QC#34087 HG-84-0387

Date Sampled: 10/17/84  
Date Reported: 11/12/84

TABULATION OF ANALYTICAL DATA FOR PESTICIDES/PCB's PER EPA METHOD 625

COMPOUND	SAMPLE I.D. - CONCENTRATION IN <del>PPM</del> PPM			
ALPHA-ENDOSULFAN	< .02			
BETA-ENDOSULFAN	< .02			
ENDOSULFAN SULFATE	< .08			
ALPHA-BHC	< .08			
BETA-BHC	< .08			
DELTA-BHC	< .08			
GAMMA-BHC	< .08			
ALDRIN	< .02			
DIELDRIN	< .02			
4,4'-DDE	< .02			
4,4'-DDD	< .02			
4,4'-DDT	< 20			
ENDRIN	< 20			
ENDRIN ALDEHYDE	< .02			
HEPTACHLOR	< .06			
HEPTACHLOR EPOXIDE	< .08			
CHLORDANE	< .40			
TOXAPHENE	< 4.0			
AROCLOR 1016	< .50			
AROCLOR 1221	< .50			
AROCLOR 1232	.90			
AROCLOR 1242	< .50			
AROCLOR 1248	< .50			
AROCLOR 1254	< .50			
AROCLOR 1260	< .50			
2,3,7,8-TETRACHLORODIBENZO- P-DIOXIN (TCDD)	Not Present			

Mercuri & Associates  
Re: QC#34087 HG-84-0387

RECEIVED  
10/10/84

ORIGINAL  
(Red)

15

TABULATION OF ANALYTICAL DATA FOR BASE/NEUTRAL EXTRACTABLES PER EPA METHOD 625

COMPOUND	SAMPLE I.D. - CONCENTRATION IN PPB
BENZO(A)PYRENE	< 100.0
INDENO(1,2,3-c)PYRENE	< 100.0
DIBENZO(A,H)ANTHRACENE	< 100.0
BENZO(G,H,I)PERYLENE	< 100.0
4-CHLOROPHENYL PHENYL ETHER	< 50.0
3,3'-DICHLOROBENZIDINE	< 50.0
BENZIDINE	< 50.0
BIS(2-CHLOROETHYL) ETHER	< 50.0
1,2-DIPHENYLHYDRAZINE	< 50.0
HEXACHLOROCYCLOPENTADIENE	< 50.0
N-NITROSODIPHENYLAMINE	< 50.0
N-NITROSODIMETHYLAMINE	< 50.0
N-NITROSODI-N-PROPYLAMINE	< 50.0
BIS(2-CHLOROISOPROPYL) ETHER	< 50.0





**QC Inc**  
QUALITY CONTROL LABORATORY

ORIGINAL  
(Red)

1205 INDUSTRIAL HIGHWAY • P.O. BOX 514 • SOUTHAMPTON, PA 18966-0514 • (215) 355-3900  
Mercuri & Associates

Re: QC#34087 HG-84-0387

Date Sampled: 10/17/84

Date Reported: 10/31/84

TABULATION OF ANALYTICAL DATA FOR VOLATILE ORGANICS PER EPA METHOD 624

COMPOUND	SAMPLE I.D. - CONCENTRATION IN PPB			
CHLOROMETHANE	< 10.0			
BROMOMETHANE	< 10.0			
VINYL CHLORIDE	< 10.0			
CHLOROETHANE	< 10.0			
METHYLENE CHLORIDE	< 10.0			
1,1, DICHLOROETHYLENE	< 10.0			
1,1, DICHLOROETHANE	< 10.0			
TRANS 1,2, DICHLOROETHYLENE	< 10.0			
CHLOROFORM	< 10.0			
1,2, DICHLOROETHANE	< 10.0			
1,1,1, TRICHLOROETHANE	< 10.0			
CARBON TETRACHLORIDE	< 10.0			
BROMODICHLOROMETHANE	< 10.0			
1,2, DICHLOROPROPANE	< 10.0			
TRANS 1,3, DICHLOROPROPENE	< 10.0			
TRICHLOROETHYLENE	< 10.0			
DIBROMOCHLOROMETHANE	< 10.0			
1,1,2, TRICHLOROETHANE	< 10.0			
CIS 1,3, DICHLOROPROPENE	< 10.0			
BENZENE	< 10.0			
2 CHLOROETHYL VINYL ETHER	< 10.0			
BROMOFORM	< 10.0			
1,1,2,2, TETRACHLOROETHANE	< 10.0			
1,1,2,2, TETRACHLOROETHYLENE	22.4			
TOLUENE	< 10.0			
CHLOROBENZENE	< 10.0			
ETHYLBENZENE	< 10.0			
ACROLEIN	< 100.0			
ACRYLONITRILE	< 100.0			
OTHER COMPOUNDS IDENTIFIED				

ORIGINAL  
(Red)

James H. H. H.  
354-0417

343-205

9-6-84

Dorsey - Bensalen Trng.

Vegetation appears to be stressed - particularly large trees  
some are dead

Ground is uneven - sinking in some spots - possibly  
landfilled

~~check for methane w/ gas tester~~  
possible pipe line through the property - gas or sewer

Keebler, ~~to~~ Rohm & Haas, Leven <sup>(next door)</sup> are only  
companies in area w/ gas

Glco (behind house) property was formerly own  
by Gus Brogger (now owned by Diguts, Inc.  
19 River Bank Rd., Beverly N.J. 08010 - Doris  
Bell - Gus Brogger's sister)

Plumbing - isn't right - he says sewer line is  
30' under ground

Trng. zoning officer - Stanley Horowitz

Galco - Bill Cousins <sup>light</sup>  
Truck leasing/rental + maintenance  
No engine overhauling - shipped in from St. Louis  
Exhaust from shop out back

TDD No.: F3-8812-06-03  
Site Name: Belco Truck Leasing

ORIGINAL  
(Red)

SITE SAFETY FOLLOW UP REPORT

Actual Date of Work: Thursday, January 5, 1989

Actual Site Investigation Team:

NUS Personnel:

[REDACTED]  
[REDACTED]  
   
   
   
   
   
   
   
 

Responsibilities:

SITL  
ASITL / 30  
   
   
   
   
   
   
   
 

Other:

Frank Bell  
   
   
   
 

Purpose:

Observe as property owner  
   
   
   
 

Team Leader:

Prepared by:

Reviewed by:

Approved by:

[REDACTED]

Date  
1/5/89  
1/5/89  
2-8-89  
2-8-89

ORIGINAL  
(Red)

F3-8812-06  
Gelco Truck Leasing

# Personal Protective Equipment

	Safety Plan Requirements		Level Used	If Deviations, explain
Activity: <u>Non-sampling site recon, photo log</u>	Respiratory Protection	D	D	None
	Field Dress	F/W	F/W	
Activity: _____	Respiratory Protection			
	Field Dress			
Activity: _____	Respiratory Protection			
	Field Dress			
Activity: _____	Respiratory Protection			
	Field Dress			
Activity: _____	Respiratory Protection			
	Field Dress			

TDD No.: E3-8812-06  
Site Name: Belco Truck Leasing

**MONITORING EQUIPMENT**

ORIGINAL  
(Red)

a. HNU

- Background reading 1.12 ppm (Industrial Park)
- Readings above background None
- Location of high readings N/A
- What action was taken? N/A

b. Radiation

- Readings above background?      Yes ✓ No
- If yes, specify where readings were found and what action was taken.

N/A

c. Heat Stress/ Cold Stress

Was heat stress or cold stress monitoring performed?

     Yes ✓ No

Was a monitoring/break schedule followed?

     Yes ✓ No

If monitoring was not performed, or the monitoring/break schedule was not followed, please explain.

Signs of cold stress were watched for, however  
field time was under 1 hour.

d. Other Monitoring Instruments None

     Draeger Tube and Pump (specify tube)     

What readings were found and what action was taken     

     Explosimeter/O<sub>2</sub> meter     

     Air Sampling

What air sampling equipment was used?

TDD No.: F3-8812-06  
Site Name: Geico Truck Leasing

ORIGINAL  
(Red)

The media used for sampling included: N/A

- ☐ Filters (type \_\_\_\_\_)
- ☐ Charcoal Tubes/Silica Gel Tubes
- ☐ Impingers (Liquid Media \_\_\_\_\_)
- ☐ Other Media

The air samples taken were ☐ environmental

N/A ☐ personal

The following team members wore personal sampling pumps.

	Team member	Location of media
1.		
2.		
3.	<u>N/A</u>	
4.		
5.		
6.		

TDD No.: E3-8812-06  
Site Name: Ex/Co Truck Leasing

GENERAL SAFETY

ORIGINAL  
(Red)

a. Were any safety problems encountered while on site?

Explain: None  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

b. Confined Space Entry

(Confined space - a tank, vessel, silo, storage bin, hopper, vault, pit, diked area, abandoned building, manhole, or any other enclosed space with limited means of exit or entry that is not designed for continuous occupancy.)

Did any team member enter a confined space area?

\_\_\_\_ Yes ☒ No

If yes, please explain.

N/A  
\_\_\_\_\_  
\_\_\_\_\_

Accident Report Information

a. Did any team member report:

Yes No

- |   |       |                                     |
|---|-------|-------------------------------------|
| • Chemical Exposure                         | _____ | <input checked="" type="checkbox"/> |
| • Illness, discomfort, or unusual symptoms  | _____ | <input checked="" type="checkbox"/> |
| • Environmental Problems (heat, cold, etc.) | _____ | <input checked="" type="checkbox"/> |

b. Explain:

N/A  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

c. Was an Employee Exposure/Injury N/A

Incident Report completed? \_\_\_\_ Yes \_\_\_\_ No



TDD No.: F3-8812-06  
Site Name: Geico Truck Leasing

ORIGINAL  
(Red)

Safety Plan Evaluation

a. Were there any deviations from the Safety Plan? ☐ Yes ☒ No

If yes, please explain. N/A  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

b. Was the Safety Plan adequate? ☒ Yes ☐ No

c. What changes would you recommend?

None  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

## NUS CORPORATION AND SUBSIDIARIES

TELECON NOTE

CONTROL NO:

8812-06-25

DATE:

1/3/89

TIME:

1530

ORIGINAL  
(Red)

DISTRIBUTION:

Gelco

BETWEEN:

Rob Allen

OF:

PAER-Norristown

PHONE:

(615) 270-1948

AND:

DISCUSSION:

Re: Site visit

Rob will be unable to accompany FIT 3 on 1/5/89 at the site due to a previous appt. at the EPA offices.

Rob suggested that I ask for him when I visit the DER office to review the files on the 2/3/89. He will help sift through the information.

[REDACTED]

1/3/89

ACTION ITEMS:

8812-06-24

## NUS CORPORATION AND SUBSIDIARIES

TELECON NOTE

CONTROL NO:

8812-06-24

DATE:

1/3/89

TIME:

1020

ORIGINAL  
(Red)

DISTRIBUTION:

Gelco

BETWEEN:

R. Allen

OF:

PADER-Norristown

PHONE:

(215) 270-1948


AND:



DISCUSSION:

Re: Site Access

Left message stating access for Gelco is Thursday January 5<sup>th</sup> at 8 in the morning. Rob only need return my call if he plans to attend or has any concerns.



ACTION ITEMS:

